



## PROJECT PROFILE

### PROJECT:

INTERMOUNTAIN MEDICAL CENTER  
Physicians & Employees Parking Structure  
Murray, Utah

### COMPLETION DATE:

FALL OF 2007

### OWNER:

INTERMOUNTAIN HEALTH CARE  
Salt Lake City, Utah

### GENERAL CONTRACTOR:

OKLAND CONSTRUCTION  
Salt Lake City, Utah



### FACILITY:

130,602 sq. ft. — 4 level post tension parking structure located at the new IMC Hospital facility.



### SCOPE OF PROJECT:

CRS was successfully awarded the contract to install a waterproofing membrane system to 3 levels of the 4 level parking structure to provide a water tight surface to protect new concrete from water and salt penetration and help prevent corrosion to post tension cables. The 3 coat system was applied with an additional intermediate aggregate wearing course to ramp drive lanes and turning radii. All cracks were routed, caulked and over-banded prior to application of the waterproofing system.



### PHOTOS:

- 1: Exterior view of parking deck.
- 2: Basecoat installed.
- 3: Intermediate coat with additional intermediate wearing course at drive lanes and turning radii.
- 4: Completed project.

